



Special applications

120 Mins+

120 Mins

90 Mins

60 Mins

30 Mins

**General Information:-**

The details shown are the assessed performance of Versafire when used in a construction using the components as identified.

The performance of the construction should satisfy the performance requirements of the BS476 part 22 for a non-load bearing construction to conform to 60 minutes integrity and insulation.

**Additional Information:-**

Steel stud partition <  
 Overall thickness 68mm <  
 Fire rating 60 mins <  
 Max centres 600mm <  
 E & OE