



Special applications

120 Mins+

120 Mins

90 Mins

60 Mins

30 Mins

**General Information :-**

The details shown are based on test report P03192ASKR confirming the performance of the Versafire/Versapanel when used in a construction using components as identified. The test was carried out in accordance to the general principles of the BS476 part 22 for non-load bearing elements of construction.

**Additional Information:-**

Steel stud partition <  
 Overall thickness 195mm <  
 Fire rating 90 mins <  
 Max centres 600mm <  
 E & OE