



Special applications

120 Mins+

120 Mins

90 Mins

60 Mins

30 Mins

### General Information:-

The details shown are the assessed performance of Versafire when used in a construction using the components as identified.

The performance of the construction should satisfy the performance requirements of the BS476 part 22 for a non-load bearing construction to conform to 120 minutes integrity and insulation.

### Additional Information:-

Steel stud partition <  
 Overall thickness 86mm <  
 Fire rating 120 mins <  
 Max centres 600mm <  
 E & OE