



Special applications

120 Mins+

120 Mins

90 Mins

60 Mins

30 Mins

**General Information:-**

The details shown are based on test report 20012572 confirming the performance of Versafire when used in a construction using components as identified. The test was carried out in accordance with the principles of test criteria GB/T 9978-1999 fire test methods of building components for non-load bearing elements of construction.

**Additional Information:-**

Steel stud partition <  
 Overall thickness 99mm <  
 Fire rating 180 mins <  
 Max centres 400mm <  
 E & OE