



Special applications

120 Mins+

120 Mins

90 Mins

60 Mins

30 Mins

General Information:-

The details shown are based on test report 20012574 confirming the performance of Versafire when used in a construction using components as identified. The test was carried out in accordance with the principles of test criteria GB/T 9978-1999 fire test methods of building components for non-load bearing elements of construction.

Additional Information:-

Steel stud partition <
 Overall thickness 140mm <
 Fire rating 240 mins <
 Max centres 400mm <
 E & OE