



Special applications

120 Mins+

120 Mins

90 Mins

60 Mins

30 Mins

General Information:-

The details shown are based on test report P03192ASKR confirming the performance of Versafire when used in a construction using the components as identified. The test was carried out in accordance to the general principles of the BS476 part 22 1987 for non-load bearing elements of construction.

Additional Information:-

Timber stud partition <
 Overall thickness 99mm <
 Fire rating 120 mins <
 Max centres 600mm <
 E & OE